

Project/ Location History

The Oklahoma Department of Transportation (ODOT) has long been considering the need to improve the narrow US-412A roadway from US-412 east to SH-10. US-412A is currently a narrow roadway with two (2) existing 12-foot-wide driving lanes with 0 to 2-foot-wide paved shoulders. The existing bridges are also narrow, with inadequate roadway geometry in places, and several skewed roadway intersection connections. These projects will upgrade the roadway to meet current Federal Highway Administration (FHWA) and Oklahoma Department of Transportation (ODOT) design standards.

Two construction projects planned in this area:

Job Piece 30373(04)

Project segment from US-412A/US-412 junction extending east 7.35 miles to State Highway 412A junction. Current construction of the Job Piece 30373(04) project is programmed to begin in fiscal year 2027.

Job Piece 30373(07)

Project segment from US-412A/State Highway 412A junction extending east 4.00 miles to State Highway 10 junction. Current construction of the Job Piece 30373(07) project is programmed to begin in fiscal year 2028.